

# CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.  
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

## OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:  
2016-122437

Date Filed:  
10/11/2016

Date Acknowledged:

**1 Name of business entity filing form, and the city, state and country of the business entity's place of business.**  
LMC Corporation  
San Antonio, TX United States

**2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.**  
Nueces County

**3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.**

101116  
Rehab of CSCD Parking Lot

4	Name of Interested Party	City, State, Country (place of business)	Nature of Interest (check applicable)	
			Controlling	Intermediary


5 Check only if there is NO Interested Party.



*Zring Kareem*

**6 AFFIDAVIT**

I swear, or affirm, under penalty of perjury, that the above disclosure is true and correct.



*Zring Kareem*  
Signature of authorized agent of contracting business entity

AFFIX NOTARY STAMP / SEAL ABOVE

Sworn to and subscribed before me, by the said Zring Kareem, this the 12 day of October, 2016, to certify which, witness my hand and seal of office.

*Megan Vance*      Megan Vance      Asst. Project Mgr.  
Signature of officer administering oath      Printed name of officer administering oath      Title of officer administering oath



**Work Order Signature Document**

<b>ezIQc Buy Board Contract No.: 2012 Area B- LMC</b>			
<input checked="" type="checkbox"/> <b>New Work Order</b>		<input type="checkbox"/> <b>Modify an Existing Work Order</b>	
Work Order Number.: 041285.00	Work Order Date: 06/15/2016		
Work Order Title: Nueces County - Rehab of an Existing Paking Lot			
Owner Name: Nueces County	Contractor Name: LMC Corporation		
Contact: Mario Garza	Contact: Zring Kareem		
Phone: 361.888.0485	Phone: 210-643-9392		

<b>Work to be Performed</b>	
Work to be performed as per the Final Detailed Scope of Work Attached and as per the terms and conditions of ezIQc Buy Board Contract No 2012 Area B- LMC.	
<u>Brief Work Order Description:</u>	
Rehab two sections of an existing parking lot.	

<b>Time of Performance</b>	Estimated Start Date:	
	Estimated Completion Date:	
<b>Liquidated Damages</b>	Will apply: <input type="checkbox"/>	Will not apply: <input checked="" type="checkbox"/>

<b>Work Order Firm Fixed Price: \$84,590.90</b>
Owner Purchase Order Number:

**Approvals**

	Date		Date
Owner		Contractor	



## Detailed Scope of Work

---

**To:** Zring Kareem  
LMC Corp - San Antonio  
10812 Hill Point  
San Antonio, TX 78217  
210-643-9392

**From:** Mario Garza  
Nueces County  
901 Leopard Street  
Corpus Christi, TX 78401  
361.888.0485

**Date Printed:** June 15, 2016

**Work Order Number:** 041285.00

**Work Order Title:** Nueces County - Rehab of an Existing Paking Lot

**Brief Scope:** Rehab two sections of an existing parking lot.

---

Preliminary

Revised

Final

---

The following items detail the scope of work as discussed at the site. All requirements necessary to accomplish the items set forth below shall be considered part of this scope of work.

### Nueces County – Rehab of an Existing parking Lot

#### Project Summary:

This scope of work applies to the Nueces County CSCD Building –parking lot Project located in Corpus Christi, TX. This project involves the rehabilitation of a parking lot. All work will be done during regular business hours, in accordance with NESHAP, EPA, OSHA, Federal and State regulation.

Provide labor, material and equipment required to:

1. Remove two concrete islands.
2. Saw cut, scarify and dispose of asphalt pavement.
3. Place limestone base.
4. Apply Prime Coat.
5. Apply Under Seal.
6. Place 3" Hot Mix Asphaltic Concrete Pavement(HMACP).
7. Lay parking stall restripe.
8. Install car stops.
9. Place Erosion Control (silt fence) around site.
10. Install barricades.
11. Clean up and haul off all debris properly and safely.

Reasonable additional, unexpected costs directly related to an existing, concealed condition or other situation that may be revealed during renovation shall be the sole responsibility of Nueces County. Further, LMC Corporation shall not be held responsible for reasonable delays caused by such condition.

Any extra work or changes to this proposal shall be determined in advance by LMC and the Project Manager or Authorized Agent. Any authorization for extra work shall show the agreed terms and costs, and be approved and signed by both parties. LMC Corporation shall do no extra work without the prior written authorization from the Project Manager or Authorized Agent.

Subject to the terms and conditions of JOC Contract 2012 Area B- LMC.

**Detailed Scope of Work Continues..**

**Work Order Number:** 041285.00

**Work Order Title:** Nueces County - Rehab of an Existing Paking Lot

---

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
Date

\_\_\_\_\_  
Owner

\_\_\_\_\_  
Date

## Contractor's Price Proposal - Summary

---

Date: June 15, 2016

Re: IQC Master Contract #: 2012 Area B- LMC  
Work Order #: 041285.00  
Owner PO #:  
Title: Nueces County - Rehab of an Existing Paking Lot  
Contractor: LMC Corporation  
Proposal Value: \$84,590.90

---

<b>Car Stop &amp; Restriping</b>	<b>\$3,779.72</b>
<b>Chain Link Fence</b>	<b>\$5,701.69</b>
<b>Demo and remove existing concrete islands</b>	<b>\$1,308.66</b>
<b>Erosion Control</b>	<b>\$283.80</b>
<b>General Division</b>	<b>\$11,084.59</b>
<b>Mobilization</b>	<b>\$11,791.19</b>
<b>Remove, Backfill And Regrade Base</b>	<b>\$16,050.98</b>
<b>Traffic Control</b>	<b>\$2,244.74</b>
<b>Underseal and Asphalt</b>	<b>\$32,345.53</b>
<b>Proposal Total</b>	<b>\$84,590.90</b>

---

This total represents the correct total for the proposal. Any discrepancy between line totals, sub-totals and the proposal total is due to rounding.

# Contractor's Price Proposal - Detail

Date: June 15, 2016

Re: IQC Master Contract #: 2012 Area B- LMC  
 Work Order #: 041285.00  
 Owner PO #:  
 Title: Nueces County - Rehab of an Existing Paking Lot  
 Contractor: LMC Corporation  
 Proposal Value: \$84,590.90

Sect.	Item	Mod.	UOM	Description	Line Total	
<b>Labor Equip. Material (Excludes)</b>						
<b>Car Stop &amp; Restriping</b>						
1	32 17 13 19 0007		EA	8" x 13" x 6' Precast Concrete Wheel Stop	\$2,759.73	
				Installation		
			Quantity	Unit Price	Factor	Total
			36.00	59.75	1.2830	2,759.73
			x	x	=	
			Install new car stop curb			
2	32 17 23 13 0066		LF	Single 4" Wide Solid Line, Painted Pavement Striping for Parking Areas	\$1,019.99	
				Installation		
			Quantity	Unit Price	Factor	Total
			1,500.00	0.53	1.2830	1,019.98
			x	x	=	
			Restripe parking spaces where necessary			
<b>Subtotal for Car Stop &amp; Restriping</b>					<b>\$3,779.72</b>	
<b>Chain Link Fence</b>						
3	32 31 13 00 0147		LF	6' Galvanized Chain Link Fence, 9 Gauge Coiled Spring Mesh, Top And Bottom Rails, 2-1/2" Line Post At 10' O.C., 3" Corner Post	\$4,706.04	
				Installation		
			Quantity	Unit Price	Factor	Total
			200.00	18.34	1.2830	4,706.04
			x	x	=	
4	32 31 13 00 0284		EA	14' Wide x 6' High Double Gate Galvanized Steel Without Barbed Wire	\$955.84	
				Installation		
			Quantity	Unit Price	Factor	Total
			1.00	745.00	1.2830	955.83
			x	x	=	
5	32 31 13 00 0609		EA	Heavy Duty Gate Latch, Malleable Galvanized Steel	\$39.81	
				Installation		
			Quantity	Unit Price	Factor	Total
			1.00	31.03	1.2830	39.81
			x	x	=	
<b>Subtotal for Chain Link Fence</b>					<b>\$5,701.69</b>	
<b>Demo and remove existing concrete islands</b>						
6	02 41 13 13 0031		SY	> 3" To 6" By Machine, Break-up And Remove Rod Reinforced Concrete Paving	\$1,308.66	
				Installation		
			Quantity	Unit Price	Factor	Total
			85.00	12.00	1.2830	1,308.66
			x	x	=	
			Break up and remove existing concrete islands			
<b>Subtotal for Demo and remove existing concrete islands</b>					<b>\$1,308.66</b>	
<b>Erosion Control</b>						
7	31 25 14 26 0015		LF	41" Total Height Super Silt Fence, 8" Below Ground, Galvanized Chain Link, With 2-1/2" Posts, 10' On Center With Geotextile Fabric Attached	\$102.38	
				Installation		
			Quantity	Unit Price	Factor	Total
			20.00	3.99	1.2830	102.38
			x	x	=	
			Erosion Control			
8	31 25 14 26 0019		LF	20" Sediment Log	\$181.42	
				Installation		
			Quantity	Unit Price	Factor	Total
			20.00	7.07	1.2830	181.42
			x	x	=	
			Erosion Control			

**Contractor's Price Proposal - Detail Continues..**

Work Order Number: 041285.00  
 Work Order Title: Nueces County - Rehab of an Existing Paking Lot

<b>Subtotal for Erosion Control</b>							<b>\$283.80</b>
<b>General Division</b>							
9	01 22 23 00 0239	WK	2,500 LB Capacity, 80" Wide, Tracked Skid-Steer Loader (Bobcat) With Full-Time Operator				\$5,952.71
		Installation	Quantity	Unit Price	Factor	Total	
			2.00 x	2,319.84 x	1.2830 =	5,952.71	
		Break up, Remove and relocate debris and material on the job site					
10	01 22 23 00 0242	WK	Hydraulic Hammer Attachment For Skid-Steer Loaders				\$1,132.12
		Installation	Quantity	Unit Price	Factor	Total	
			2.00 x	441.20 x	1.2830 =	1,132.12	
		Break up, Remove and relocate debris and material on the job site					
11	01 22 23 00 0245	WK	Forklift Attachment For Skid-Steer Loaders				\$317.54
		Installation	Quantity	Unit Price	Factor	Total	
			2.00 x	123.75 x	1.2830 =	317.54	
		Break up, Remove and relocate debris and material on the job site					
12	01 74 19 00 0013	EA	20 CY Dumpster (3 Ton) *Construction Debris*Includes delivery of dumpster, rental cost, pick-up cost, hauling, and disposal fee. Non-hazardous material.				\$2,238.84
		Installation	Quantity	Unit Price	Factor	Total	
			5.00 x	349.00 x	1.2830 =	2,238.83	
		Dumpster for the job site					
13	01 74 19 00 0029	CYM	Hauling On Paved Roads, First 15 Miles				\$1,443.38
		Installation	Quantity	Unit Price	Factor	Total	
			2,500.00 x	0.45 x	1.2830 =	1,443.37	
		Haul off fee					
<b>Subtotal for General Division</b>							<b>\$11,084.59</b>
<b>Mobilization</b>							
14	01 22 23 00 0178	WK	8 Ton, Single Smooth Drum, Ride-On Self-Propelled Vibratory Roller With Full-Time Operator				\$3,227.23
		Installation	Quantity	Unit Price	Factor	Total	
			1.00 x	2,515.38 x	1.2830 =	3,227.23	
		Compact existing base and new asphalt					
15	01 22 23 00 0521	WK	60 HP Road Grader With Full-Time Operator				\$3,175.36
		Installation	Quantity	Unit Price	Factor	Total	
			1.00 x	2,474.95 x	1.2830 =	3,175.36	
		Regrade existing base					
16	01 71 13 00 0003	EA	Equipment Delivery, Pickup, Mobilization And Demobilization Using A Tractor Trailer With Up To 53' BedFor equipment such as bulldozers, motor scrapers, hydraulic excavators, gradalls, road graders, loader-backhoes, heavy duty construction loaders, tractors, pavers, rollers, bridge finishers, straight mast construction forklifts, telescoping boom rough terrain construction forklifts, telescoping and articulating boom manlifts with > 40' boom lengths, etc.				\$5,388.60
		Installation	Quantity	Unit Price	Factor	Total	
			14.00 x	300.00 x	1.2830 =	5,388.60	
		Equipment and dumpster delivery					
<b>Subtotal for Mobilization</b>							<b>\$11,791.19</b>
<b>Remove, Backfill And Regrade Base</b>							

**Contractor's Price Proposal - Detail Continues..**

Work Order Number: 041285.00  
 Work Order Title: Nueces County - Rehab of an Existing Paking Lot

<b>Remove, Backfill And Regrade Base</b>									
17	02	41	13	13	0019	SY	Up To 3" By Machine, Break-up And Remove Bituminous Paving		\$10,854.18
						Installation	Quantity	Unit Price	Factor = Total
							1,500.00	5.64	1.2830 = 10,854.18
							Break up and remove existing asphalt		
18	02	41	19	13	0034	LF	Saw Cut In Streets, Concrete And Asphalt Up To 4" Depth		\$1,552.43
						Installation	Quantity	Unit Price	Factor = Total
							1,100.00	1.10	1.2830 = 1,552.43
							Sawcut existing asphalt		
19	02	41	19	13	0034 0030		For Each Additional Pass (Depth To 3"), Add		\$536.29
						Installation	Quantity	Unit Price	Factor = Total
							1,100.00	0.38	1.2830 = 536.29
20	31	23	16	33	0004	CY	Bulk Excavation by Dozer in Loose Rock		\$286.75
						Installation	Quantity	Unit Price	Factor = Total
							50.00	4.47	1.2830 = 286.75
							Excavate, backfill and compact existing base where necessary		
21	31	23	16	33	0007	CY	Spreading, Shaping, and Rough Grading Imported or Stockpiled Material for Bulk Excavation by Machine		\$143.70
						Installation	Quantity	Unit Price	Factor = Total
							50.00	2.24	1.2830 = 143.70
							Excavate, backfill and compact existing base where necessary		
22	31	23	16	33	0009	CY	Cutting, Shaping and Rough Grading Existing Elevations For Bulk Excavation by Machine		\$159.73
						Installation	Quantity	Unit Price	Factor = Total
							50.00	2.49	1.2830 = 159.73
							Excavate, backfill and compact existing base where necessary		
23	31	23	16	33	0011	CY	Relocating On Site Excavated Material From Bulk Excavation Over 100' to 300'		\$127.66
						Installation	Quantity	Unit Price	Factor = Total
							50.00	1.99	1.2830 = 127.66
							Excavate, backfill and compact existing base where necessary		
24	31	23	16	33	0016	SY	Finish Grading for Bulk Excavation by Machine		\$481.13
						Installation	Quantity	Unit Price	Factor = Total
							1,500.00	0.25	1.2830 = 481.12
							Excavate, backfill and compact existing base where necessary		
25	31	23	16	33	0018	SY	Compaction of Fill or Subbase for Bulk Excavation by Machine Per Lift		\$442.64
						Installation	Quantity	Unit Price	Factor = Total
							1,500.00	0.23	1.2830 = 442.63
							Excavate, backfill and compact existing base where necessary		
26	31	23	16	33	0020	CY	Loading Excess Material For Removal From Bulk Excavation		\$177.05
						Installation	Quantity	Unit Price	Factor = Total
							50.00	2.76	1.2830 = 177.05
							Excavate, backfill and compact existing base where necessary		
27	32	11	16	00	0008	SY	4" Crushed Aggregate Base Course		\$1,289.42
						Installation	Quantity	Unit Price	Factor = Total
							250.00	4.02	1.2830 = 1,289.41
							Excavate, backfill and compact existing base where necessary		
<b>Subtotal for Remove, Backfill And Regrade Base</b>									<b>\$16,050.98</b>

**Traffic Control**



**Contractor's Price Proposal - Detail Continues..**

**Work Order Number:** 041285.00  
**Work Order Title:** Nueces County - Rehab of an Existing Paking Lot

<b>Traffic Control</b>							
28	01 55 26 00 0016	MO	28" Cone With Reflective Collar				\$1,667.39
		Installation	Quantity	Unit Price	Factor	Total	
			360.00	3.61	1.2830	1,667.39	
			x	x	=		
29	01 55 26 00 0089	EA	Place And Remove Up To 250 Cones Using Truck				\$577.35
		Installation	Quantity	Unit Price	Factor	Total	
			360.00	1.25	1.2830	577.35	
			x	x	=		
<b>Subtotal for Traffic Control</b>							<b>\$2,244.74</b>
<b>Underseal and Asphalt</b>							
30	32 12 13 19 0001	SY	Surface Prime Coat, 0.28 Gallon/SY				\$1,770.54
		Installation	Quantity	Unit Price	Factor	Total	
			1,500.00	0.92	1.2830	1,770.54	
			x	x	=		
		Apply Prime coat					
31	32 12 16 13 0013	TON	Bituminous Hot Mix Surface Course 3774 LB/CY Includes placement, rolling, finishing and sweeping. Used for applications not described elsewhere in this section.				\$28,977.65
		Installation	Quantity	Unit Price	Factor	Total	
			235.00	96.11	1.2830	28,977.65	
			x	x	=		
		Place 3" Hot mix					
32	32 12 36 00 0037	SY	> 500 To 1100 SY Fog Seal, SS-1				\$1,597.34
		Installation	Quantity	Unit Price	Factor	Total	
			1,500.00	0.83	1.2830	1,597.33	
			x	x	=		
		Apply Underseal coat					
<b>Subtotal for Underseal and Asphalt</b>							<b>\$32,345.53</b>
<b>Proposal Total</b>							<b>\$84,590.90</b>

This total represents the correct total for the proposal. Any discrepancy between line totals, sub-totals and the proposal total is due to rounding.



## Subcontractor Listing

Date: June 15, 2016

Re: IQC Master Contract #: 2012 Area B- LMC  
Work Order #: 041285.00  
Owner PO #:  
Title: Nueces County - Rehab of an Existing Paking Lot  
Contractor: LMC Corporation  
Proposal Value: \$84,590.90

Name of Contractor	Duties	Amount	%
No Subcontractors have been selected for this Work Order		\$0.00	0.00